

SHIMOGA DIVISION.

Dated 6th November 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 5 P.M., on 2nd December 1912, for restoring Mallur Oorumundinkere, Shikarpur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Mallur Oorumundinkere, Shikarpur Taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract quantity of establishment for restoring Mallur Oorumundinkere, Shikarpur Taluk.

No.	Items of work.	Per	Quantity.
<i>Bund—</i>			
1.	Earthwork to bund gravelly soil watering and tamping ...	C. yd.	15,487
2.	Turfing ...	S. yd.	16,142
3.	Grade stones including bed slabs ...	Each.	28
4.	Index stones ...	"	28
5.	B. M. stones ...	"	2
6.	Date stone ...	"	1
7.	Register No. stone ...	"	1
8.	Gauge stone ...	"	1
<i>No. 1. Sluice—</i>			
9.	Repairing and providing iron rod, etc. ...	Lump sum rupees.	
<i>No. 2. Sluice—</i>			
10.	Earthwork cutting bund and filling the same with consolidation.	C. yd.	138
11.	Earthwork excavation ...	"	13
12.	Concrete in surki mortar ...	C. ft.	31
13.	Burnt brick in surki mortar ...	"	619
14.	Burnt stone slabs, dressed ...	S. ft.	112
15.	Plastering with surki mortar ...	Sq.	520
16.	Fitting cast iron pipes, 6" diametre, including Railway freight and cart hire from Railway station to site.	R. ft.	45
17.	Fixing wooden plug with iron rods, etc., complete ...	Lump sum rupees.	
18.	Cutting orifice stone guide and top stone ...	"	"
<i>Left waste weir 130. feet—</i>			
19.	Earthwork excavation ...	C. yd.	832
20.	Burnt brick in surki mortar ...	C. ft.	1,655
21.	Burnt stone slabs dressed and fitted ...	S. ft.	507
22.	Plastering with surki mortar ...	Sq.	19.93
23.	Rough stone sugicut work including bed ...	C. yd.	286
24.	Turfing the slopes of training bank slopes ...	Sq.	1.50

V. R. NIJAGAL,
Executive Engineer.